

United Property Resource Corporation

Norval United Church

Stormwater Management Report

July 14, 2023





Norval United Church

Stormwater Management Report

United Property Resource Corporation

Project No.: 221-05336-00

Date: July 14, 2023

WSP

100 Commerce Valley Drive West

Thornhill, ON

Canada L3T 0A1

T: +1 905 882-1100

F: +1 905 882-0055

wsp.com

Revision History

FIRST ISSUE

| | |
|-------------------------------|--|
| 12/16/2022 | ZBA |
| Prepared by | Reviewed / Approved by |
| Lanxin Zhang, Designer E.I.T. | Alyssa Mohino-Barrie, Senior Project Manager |

REVISION 1

| | |
|-------------------------------|-------------------------------------|
| 07/14/2023 | ZBA |
| Prepared by | Reviewed / Approved by |
| Lanxin Zhang, Designer E.I.T. | Tahmineh Sarabian, Project Engineer |

REVISION 2

| | |
|------------------|-------------------|
| <Date> | <Remarks> |
| Prepared by | Reviewed by |
| <prepare, title> | <reviewer, title> |

FINAL

| | |
|------------------|-------------------|
| <Date> | <Remarks> |
| Prepared by | Reviewed by |
| <prepare, title> | <reviewer, title> |

Signatures

Prepared by

Lanxin Zhang

2023-07-14

Lanxin Zhang, E.I.T.
Designer, Land Development

Date

Approved¹ by



Tahmineh Sarabian, P.Eng.
Project Engineer, Water Resources

Date

WSP Canada Inc (WSP) prepared this report solely for the use of the intended recipient, United Property Resource Corporation, in accordance with the professional services agreement. The intended recipient is solely responsible for the disclosure of any information contained in this report. The content and opinions contained in the present report are based on the observations and/or information available to WSP at the time of preparation. Other than the Town of Halton Hills and its Agents, who may rely on the contents of this report, if a third party makes use of, relies on, or makes decisions in accordance with this report, said third party is solely responsible for such use, reliance or decisions. WSP does not accept responsibility for damages, if any, suffered by any third party as a result of decisions made or actions taken by said third party based on this report. This limitations statement is considered an integral part of this report.

The original of this digital file will be conserved by WSP for a period of not less than 10 years. As the digital file transmitted to the intended recipient is no longer under the control of WSP, its integrity cannot be assured. As such, WSP does not guarantee any modifications made to this digital file subsequent to its transmission to the intended recipient.

¹ Approval of this document is an administrative function indicating readiness for release and does not impart legal liability on to the Approver for any technical content contained herein. Technical accuracy and fit-for-purpose of this content is obtained through the review process. The Approver shall ensure the applicable review process has occurred prior to signing the document.

Contributors

Client

United Property Resource Corporation

WSP

Designer, Land Development

Lanxin Zhang

Project Engineer, Water Resources

Tahmineh Sarabian

Senior Project Manager, Water Resources

Alyssa Mohino Barrie

Senior Project Manager, Land Development

Peter Cane

Proof (non-technical) / Format

Melinda Nowak



TABLE OF CONTENTS

| | | |
|----------|---|-----------|
| 1 | INTRODUCTION..... | 1 |
| 1.1 | Scope | 1 |
| 1.2 | Site Location..... | 1 |
| 1.3 | Stormwater Management Plan Objectives..... | 3 |
| 1.4 | Design Criteria..... | 3 |
| 2 | EXISTING CONDITIONS | 5 |
| 2.1 | General | 5 |
| 2.2 | Rainfall Information..... | 5 |
| 2.3 | Allowable Flow Rates | 8 |
| 3 | POST-DEVELOPMENT CONDITIONS..... | 9 |
| 3.1 | General | 9 |
| 3.2 | Water Balance..... | 11 |
| 3.3 | Water Quality Control | 11 |
| 3.4 | Erosion Control..... | 11 |
| 3.5 | Water Quantity Control | 11 |
| 4 | EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION | 14 |
| 5 | CONCLUSIONS..... | 15 |
| | BIBLIOGRAPHY | 16 |

Tables

| | | |
|------------|--|----|
| Table 2-1: | Rainfall Parameters..... | 6 |
| Table 2-2: | Pre-Development Peak Flow Rates..... | 8 |
| Table 3-1: | Proposed Conditions Area Breakdown | 9 |
| Table 3-2: | Summary of Modelling Results | 12 |

Figures

| | | |
|-----------|---------------------------|----|
| Figure 1: | Site Location..... | 2 |
| Figure 2: | Existing Conditions..... | 7 |
| Figure 3: | Proposed Conditions | 10 |

Appendices

| | |
|----------|--------------------------------------|
| A | Existing Drainage Plan |
| B | Stormwater Management Calculations |
| C | Water Quality Treatments Units |
| D | Hydrological Model Output (HydroCAD) |

1 INTRODUCTION

1.1 Scope

WSP Canada Inc. (WSP) has been retained by United Property Recourse Corporation to prepare a Stormwater Management (SWM) Report to support the Zoning By-law Amendment (ZBA) application of the proposed development located at 14015 Danby Road in the Town of Halton Hills (hereafter the “site”). A portion of the site includes an existing church building serviced by two underground storm tanks. The church building and its stormwater management system, including service connections, will not be altered as part of this development, and therefore is excluded from the site area and the analysis provided in this report. The scope of this report is limited to the parts of the site area which will be altered, developed and/or reconstructed, this area is referred to as the “development boundary” hereafter.


This SWM report examines the potential water quantity and water quality impacts of the proposed development and summarizes how each will be addressed in conformance with the requirements of the Town of Halton Hills, Conservation Halton (CH) and other applicable stormwater management criteria.

1.2 Site Location

The site has an area of 2.00 ha, located at the existing Norval United Church at 14015 Danby Road in the Town of Halton Hills, Region of Halton. As noted in **Section 1.1**, the development boundary excludes the existing church, and therefore has an area of 1.85 ha.

The site is a part of the Fernbrook Mountainview subdivision development. More subdivision design details can be referenced in the previous design from Fernbrook Mountainview – Phase 3 Stormwater Management Report (the “FM Report”), dated February 2014, by The Sernas Group Inc.

The site is generally trapezoid in shape and has Victory Fellowship Church to the North, Eight Line to the West, and Danby Road to the South and East. The location of the proposed development is illustrated in **Figure 1**. The site lies within the Sixteen Miles Creek sub-watershed, which is under the jurisdiction of CH.




@2023 Google - Map data @2023

FIGURE 1.dwg Site Location C:\Users\katz077846\ACCDocs\WSP Canada projects (AMER)\LDOFiles\221-05336 Norval United Church\SWMF\Figures\ Jul 06, 2023 - 5:04pm

CLIENT
UNITED PROPERTY RESOURCE CORPORATION

TITLE
NORVAL UNITED CHURCH,
TOWN OF HALTON HILLS

SITE LOCATION

| | | | |
|---|-----------|------------|--------------|
|  | | | |
| Checked | T.S. | Drawn | AutoCAD/L.Z. |
| Date | JULY 2023 | Proj. No. | 221-05336-00 |
| Scale | N.T.S. | Figure No. | 1 |
| | | Gr.No. | . |

1.3 Stormwater Management Plan Objectives

In accordance with the applicable Town of Halton Hills and Conservation Halton's SWM guidelines, the objectives of this stormwater management plan are as follows:

- Determine site specific stormwater management requirements to ensure that the development project is in conformance with the Town and Conservation guidelines.
- Evaluate various stormwater management practices that meet the requirements of the relevant SWM design criteria and recommend a preferred strategy.
- Prepare a stormwater management report documenting the strategy along with the technical information necessary for sizing the proposed stormwater management features.

1.4 Design Criteria

CH issued the Stormwater Management Engineering Submission Guidelines document in November 2021 to identify the Conservation's regulatory and technical requirements for any SWM submission within its jurisdiction as well as to outline its key expectations for SWM designs. In addition, design criteria from the high-level subdivision plan, FM Report, is used to determine the specific objectives for the proposed development. As such, a summary of the stormwater management criteria applicable to this project is as follows:

Water Balance

The Guidelines recommend that the levels shall be maintained as close to current levels as possible to reduce impacts on surface water and groundwater systems. According to the Guidelines, the water balance / infiltration strategies should consider both site scale and feature-based scale.

Currently, due to the absence of criteria specified in the higher-level study, the proponent is recommended to retain the minimum 5 mm rainfall event.

Water Quality

Under the FM Report, the site is required to target a long-term removal of 80% of total suspended solids (TSS) on an annual loading basis, and ensure water discharged to the municipal storm sewers is in compliance with all town requirements pertaining to water quality control.

Erosion Control

Under the FM Report, a minimum 24-hour detention of runoff from a 4 hour 25 mm storm shall be provided for extended detention / erosion protection. However, for a small infill / redevelopment sites <2 ha, erosion control in the form of stormwater detention is normally not required, provided a on-site minimum runoff retention from a small design rainfall event (typically 5 mm) is achieved.

Water Quantity Control and Discharge to Municipal Infrastructure

As indicated in the FM Report, there is an existing online stormwater quantity control facility located upstream of the site within Sixteen Mile Creek lands. The stormwater quantity control facility has been sized to accommodate all runoff from the site, assuming industrial land use and an imperviousness of 40%. As such, additional quantity controls measures are required for the site when the imperviousness of the proposed development exceeds 40%.

As a conservative measure, runoff from the 2-year up to 100-year design storms will be controlled to the 5-year pre-development flow rate released into the municipal storm sewer system assuming an imperviousness of 40%.

2 EXISTING CONDITIONS

2.1 General

The site is a development located at the northeast corner of Eight Line – Danby intersection. The existing overland flow route is directed northeast towards the southeast corner of the site and flows east along Danby Road. The 1.85 ha development boundary is currently occupied by an at-grade parking, paved surfaces, and landscaping areas.

The existing runoff coefficient for the site is estimated to be $C = 0.48$ per Urbantech design from 2019, rev 8, dated Feb 5, 2019. The existing storm drainage plan can be found in **Appendix A**.

An existing runoff coefficient of 0.45 is estimated for the development boundary. Under the existing conditions, the development boundary does not receive runoff from other areas of the site or external drainage areas.

The existing condition of the site is shown in Error! Reference source not found..

2.2 Rainfall Information

The rainfall intensity for the site was calculated using the following equation:

$$I = A/(B + T)$$

Where,

I = rainfall intensity in mm/hour

T = time of concentration in minutes

A, B, and C = constant parameters (see below)

The parameters (A, B, C) recommended for use by Conservation Halton are summarized in **Table 2-1**.



Table 2-1: Rainfall Parameters

| Return Period (Years) | 2 | 5 | 10 | 25 | 50 | 100 |
|------------------------------|----------|----------|-----------|-----------|-----------|------------|
| A | 586.10 | 946.46 | 1173.48 | 1368.91 | 1622.45 | 1777.2 |
| B | 6.0 | 7.0 | 8.0 | 8.0 | 9.0 | 9.0 |
| C | 0.760 | 0.788 | 0.794 | 0.789 | 0.797 | 0.795 |

Source: Conservation Halton Guidelines for Stormwater Management Engineering Submissions

Gauge: Town of Halton Hills

An initial time of concentration, T_c , of 10 minutes (or 0.167 hours) is recommended for this site.



Eight Line

Danby Road

LEGEND

- PROPERTY BOUNDARY
- CONTROLLED DRAINAGE AREA
- Existing Site (Excluded)
- At-Grade Impervious
- At-Grade Landscaping
- DRAINAGE AREA (ha)
- AVERAGE RUNOFF COEFFICIENT

| | | | |
|--------|---|--|--|
| CLIENT | UNITED PROPERTY RESOURCE CORPORATION | | |
| TITLE | NORVAL UNITED CHURCH, TOWN OF HALTON HILLS | | |
| | EXISTING CONDITIONS | | |



| | | | |
|---------|-----------|------------|--------------|
| Checked | T.S. | Drawn | AutoCAD/L.X. |
| Date | JULY 2023 | Proj. No. | 221-05336 |
| Scale | 1:500 | Figure No. | 2 |
| | | Gr.No. | |

FIGURE 2: re.dwg FC2 C:\Users\kai077946\OneDrive\WSP\Canada_projects\AMER\LOI\Files\221-05336-Norval United Church\SWM\Figures\ Jul 13, 2023 - 6:09pm

2.3 Allowable Flow Rates

The site is located in an area of suburban development. As noted in **Section 1.3**, relevant policies from the Town require the discharge rate from this site to be controlled to the allowable rate for discharge to municipal sewers. The allowable release rate is the 5-year pre-development flow rate to the municipal storm sewer system assuming an imperviousness of 40% ($C = 0.48$).

The runoff coefficient for the 1.85 ha development boundary under existing conditions is $C = 0.45$. The pre-development peak flow rates from the development boundary are summarized in **Table 2.2**. Detailed calculations are contained within **Appendix B**.

Table 2-2: Pre-Development Peak Flow Rates

| Return Period (Years) | Rainfall Intensity, I (mm/hr) | Pre-Development Peak Flow Rates ¹ (L/s) | Allowable Release Rate ² (L/s) |
|-----------------------|-------------------------------|--|---|
| 2 | 71.3 | 175.7 | 250.3 |
| 5 | 101.5 | 250.3 | |
| 10 | 118.2 | 291.6 | |
| 25 | 139.9 | 345.1 | |
| 50 | 155.2 | 382.9 | |
| 100 | 171.1 | 421.9 | |

¹ Based off a runoff coefficient Imperviousness = 40% ($C = 0.48$), an area of 1.85 ha for the development boundary, and a T_c of 10 minutes

² 5-year peak flow based off a runoff coefficient Imperviousness = 40% ($C = 0.48$), an area of 1.85 ha and a T_c of 10 minutes

3 POST-DEVELOPMENT CONDITIONS

3.1 General

The proposed development consists of the construction of a new condominium and an underground parking in the north section of the site, north of the existing building. Access to the site will be provided by two entrances, the first entrance off of Danby Road, and the second off of Eight Line.

Runoffs generated from the development area will be collected and directed to a stormwater tank located underneath the surface parking lot adjacent to Danby Road which will drain to the existing storm sewer on Danby Road. **Figure 3** illustrates the proposed conditions.



The subject development boundary has a weighted runoff coefficient of 0.70 and an imperviousness of 69% under post-development conditions. An area breakdown of the purposed development is provided below in **Table 3-1**.

Table 3-1: Proposed Conditions Area Breakdown









| Surface Type | Area (m ²) | Runoff Coefficient, C | Impervious | % Coverage |
|--------------------------|------------------------|-----------------------|------------|-------------|
| Impervious Roof Coverage | 2,344 | 0.90 | 100% | 13% |
| Landscaping | 5,782 | 0.25 | 0% | 31% |
| At-grade Impervious | 10,356 | 0.90 | 100% | 56% |
| Total Area | 18,482 | 0.70 | 69% | 100% |

FIGURE 3.dwg: F03 C:\Users\cal07749\A\CC\Des\WSP_Canada_projects\AMER\LD\Files\221-05336\Norval United Church\SWM\Figures\ Jul 13, 2023 - 5:56pm

Eight Line



LEGEND

-  PROPERTY BOUNDARY
-  CONTROLLED DRAINAGE AREA
-  Impervious Roof
-  At-Grade Impervious
-  At-Grade Landscaping
-  Existing Site (Excluded)
-  DRAINAGE AREA (ha)
-  AVERAGE RUNOFF COEFFICIENT

CLIENT
UNITED PROPERTY RESOURCE CORPORATION

TITLE
NORVAL UNITED CHURCH,
TOWN OF HALTON HILLS

PROPOSED CONDITIONS



| | |
|-------------------|----------------------------|
| Checked T.S. | Drawn AutoCAD/L.X. |
| Date JULY 2023 | Proj. No. 221-05336 |
| Scale 1:500 | Figure No. 3 Gr.No. |

3.2 Water Balance

The development boundary shall target the retention of the 5 mm rainfall event for the purpose of water balance. A minimum volume of 50.08 m³ shall be retained for reuse within the stormwater tank, below the outlet. The reuse methods for the captured stormwater will be assessed in conjunction with the mechanical design of the building's water supply systems. The overall proposed reuse options include irrigation of landscaping areas, fixture flushing and any additional non-potable demand in the communal building areas. It is assumed that sufficient opportunities exist within the development to reuse the full volume of retained stormwater within a 72-hour period.

3.3 Water Quality Control

Stormwater runoff from the development boundary will require water quality treatment. This will provide pre-treatment for the water balance volume and ensure excessive sediment does not accumulate within the tank. The standard for water quality treatment is 80% TSS removal on a long-term average annual loading basis. A water quality unit, Imbrium Jellyfish Filter model JF6-6-1, has been sized to provide treatment to the 1.04 ha of at-grade impervious area. Details are included under **Appendix C**.

3.4 Erosion Control

As mentioned in **Section 1.3**, this development has an overall small footprint, and the 5 mm water balance volume has been retained, thus no further erosion control measures are recommended at this stage beyond the erosion and sediment controls implemented during construction. If required, the Town and the Conservation staff may provide consultation on additional site-specific controls upon review.

3.5 Water Quantity Control

Section 1.4 noted, quantity controls are required for the site when the imperviousness of the proposed development exceeds 40%. The subject development area has a weighted imperviousness of 40% under post-development conditions. Therefore, additional quantity control is required for the development boundary. Per **Section 2.3**, the development boundary discharge to the Danby Road storm sewer must be controlled to the allowable discharge rate of 250.3 L/s. This is equivalent to the peak runoff rate under pre-development conditions during a 5-year design storm event using an imperviousness of 40% (a runoff coefficient of 0.48).

The 'HydroCAD' software package (Version 10) has been used to model the behaviour of the proposed SWM system and determine its response under various storm events. This software utilizes the Modified Rational Method to calculate flow rates and related required storage values under all storm events. The.

An emergency overflow will be provided at the top of the tank, with discharge to street level and the adjacent right of way. This will prevent flow from backing up into the building pipework if the primary outlet is blocked, or if a storm event in excess of the 100-year return period occurs.

The runoff from the development boundary will be collected into a stormwater tank underneath the surface parking lot adjacent to Danby Road. The tank was modelled with a base area of 270.0 m² and a height of 1.4 m, providing 378.0 m³ of storage.

The potential reuse volume for water balance is contained below the outlet invert, at 0.20 m, and is assumed full at the onset of each storm event. The provided sump volume of 54.0 m³ satisfies the water balance criterion. A 300 mm orifice tube is proposed as the outlet control and provides sufficient flow restriction to control release rates to the target rate set by the Town.

A summary of the modelling results is provided below in **Table 3-2**. Full HydroCAD modelling output is provided in **Appendix D**.

Table 3-2: Summary of Modelling Results

| Return Period (Years) | Allowable Release Rate (L/s) | Peak Tank Discharge Rate (L/s) | Utilized Storage (of 378 m ³) | Water Depth in Tank (m) |
|-----------------------|------------------------------|--------------------------------|---|-------------------------|
| 2 | 250.3 | 124.0 | 157.5 | 0.583 |
| 5 | | 164.4 | 205.2 | 0.760 |
| 10 | | 186.3 | 236.7 | 0.877 |
| 25 | | 211.1 | 277.0 | 1.026 |
| 50 | | 229.6 | 310.5 | 1.150 |
| 100 | | 246.2 | 342.8 | 1.270 |

The modelling results demonstrate that the post-development peak flow rates for all events up to and including the 100-year storm are lower than the target release rate established in accordance with the Guidelines. The maximum required storage volume to control the 100-year post-development runoff is 342.8 m³. Note that this total utilized

storage volume includes the previously quoted sump storage volume, and the sump has been modelled as full at the beginning of the storm event.

The storm duration producing the highest combination of peak flows from the tank has been iteratively determined to be $t_d = 24$ minutes (for the 100-year event) according to the modified rational method.

4 EROSION AND SEDIMENT CONTROL DURING CONSTRUCTION

During construction, there is potential for short-term sediment wash-off from the site. To protect the downstream receiving sewer system and other natural features, on-site sediment control measures are necessary during construction.

As sediment and erosion control strategies focus on minimizing adverse environmental impacts by restricting the mobilization and transport of sediment, the following general practices will be observed:

- Sediment and erosion control works, as shown on the site's erosion and sedimentation control plans which will be provided during the detailed design stage, must be in place prior to the commencement of construction, and not removed until the end of the construction period, when the site has been stabilized.
- Construction phasing must be scheduled to minimize the extent and period to which disturbed soils are exposed to weathering. As such, all disturbed areas must be stabilized as quickly as possible. Stabilization of disturbed areas may be accomplished by sodding, seeding, mulching, hydroseeding, planting, or covering of constructed slopes with an appropriate material such as geotextile or jute mesh.
- Access to the construction site must be minimized.
- A continuous siltation fence must be constructed along the perimeter of the proposed development. The silt fence must be in place prior to the commencement of construction, and must be removed at the end of the construction period.

5 CONCLUSIONS

A stormwater management plan has been prepared to support the ZBA application for the proposed development of the Norval United Church in the Town of Halton Hill. The key points are summarized below.

Water Balance

The overall proposed reuse options include irrigation and flushing of toilets and any additional non-potable demand in the communal building areas. The provided sump volume below the outlet of the cistern is enough to satisfy the water balance criterion.

Water Quality

A water quality unit, Imbrium Jellyfish Filter model JF6-6-1, is sized to provide treatment for the at-grade impervious areas and shall treat runoff from these areas to an 80%TSS removal on an average annual basis.

Erosion Control

The development boundary achieves retention of the 5 mm rainfall event, thus no further erosion controls beyond erosion and sediment controls implemented during construction.

Water Quantity

Runoff from the controlled catchments on-site will be directed to a stormwater tank. Post-development flows in the development boundary have been controlled to below 250.3 L/s, in compliance with the target release rate to the municipal storm sewer system by use of a 378.0 m³ stormwater tank fitted with a 300 mm orifice outlet.

The proposed SWM strategy described in this report addresses all stormwater management-related impacts from the project and satisfies the intent of the Town and the Conservation's regulatory and technical requirements.

BIBLIOGRAPHY

- Conservation Halton Guidelines for Stormwater Management Engineering Submissions. Retrieved December 14, 2022, https://www.conservationhalton.ca/wp-content/uploads/2022/05/CH_GSWMES_Nov2021_Final.pdf
- Fernbrook Mountainview – Phase 3 Stormwater Management Report. The Sernas Group Inc. June 2013 (Revised February 2014). Retrieved May 31, 2023.

APPENDIX







A

Existing Drainage Plan





NOTE: REFER TO FERNBROOK HOMES MOUNTAINVIEW PH3 DRAWINGS (PROJECT NO. 11142) BY GHD FOR SERVICE CONNECTIONS DETAILS.

| Surface type | "C" | Area (ha) |
|--------------------------|-------------|-------------|
| | 1 | 0.25 |
| | 2 | 0.41 |
| | 3 | 0.25 |
| | 4 | 0.90 |
| | 5 | 0.90 |
| | 6 | 0.63 |
| | 7 | 0.82 |
| | 8 | 0.52 |
| | 9 | 0.72 |
| | 10 | 0.70 |
| | 11 | 0.80 |
| | 12 | 0.25 |
| | 13 | 0.90 |
| Composite C Value | 0.48 | 2.01 |



urbantech
Urbantech Consulting, A Division of Leighton-Zee Ltd.
 3700 14th Avenue, Suite 201, Markham, Ontario L3R 3T7
 Tel: 905.949.4141 Fax: 905.949.0999
 www.urbantech.com



MAIN STREET / EIGHTH LINE

DANBY ROAD

SIERRA CRESCENT

SIERRA CRESCENT

NORVAL UNITED CHURCH PHASE 1
 F.F.E. = 244.50

APPENDIX

B

Stormwater Management Calculations



| | | | |
|----------|----------------------|----------|------------|
| Project: | Norval United Church | No.: | 211-05336 |
| By: | LZ | Date: | 2023-07-13 |
| Checked: | TS | Checked: | TS |
| | | | Page: |
| | | | 1 |

Subject: Stormwater Management Calculations - Existing Discharge Rate

Calculation of existing runoff rate is undertaken using the Rational Method: **Q = 2.78 CIA**

- Where: Q = Peak flow rate (litres/second)
 C = Runoff coefficient
 I = Rainfall intensity (mm/hour)
 A = Catchment area (hectares)

Catchment Area, A **1.85** hectares
 * Runoff Coefficient, C 0.48
 Imperviousness 0.40

$$I = A / (B + t)^C \quad \text{IMPERVIOUSNESS} = (C - 0.2) / 0.7$$

Rainfall intensity calculated in accordance with the Town Requirements:

- Where: A, B and C = Parameters defined in requirements
 I = Rainfall intensity (mm/hour)
 T = Time of concentration (mins)

| Return Period (Years) | 2 | 5 | 10 | 25 | 50 | 100 |
|-----------------------|--------|--------|---------|---------|---------|--------|
| A | 586.1 | 946.46 | 1173.48 | 1368.91 | 1622.45 | 1777.2 |
| B | 6 | 7 | 8 | 8 | 9 | 9 |
| C | -0.76 | -0.788 | -0.794 | -0.789 | -0.797 | -0.795 |
| T (mins) ** | 10 | 10 | 10 | 10 | 10 | 10 |
| T (hrs) | 10.000 | 10.000 | 10.000 | 10.000 | 10.000 | 10.000 |
| I (mm/hr) | 71.3 | 101.5 | 118.2 | 139.9 | 155.2 | 171.1 |
| Q (litres/sec) | 175.7 | 250.3 | 291.6 | 345.1 | 382.9 | 421.9 |
| Q (m3/sec) | 0.176 | 0.250 | 0.292 | 0.345 | 0.383 | 0.422 |

Allowable release rate to municipal storm sewer system is therefore 250.3 litres/second.

Source: Conservation Halton Guidelines for Stormwater Management Engineering Submissions
 Gauge: AES for Toronto International Airport, Fergus Shand Dam and Heart Lake



| | | |
|--------------------------------------|-------------------------|-------------------|
| Project: Norval United Church | No.: 221-05336 | Page: 2 |
| By: LZ | Date: 2023-07-13 | |
| Checked: TS | Checked: TS | |

Subject: Stormwater Management Calculations - Water Balance Calculations

The Town require a site "to retain water on-site to the extent practicable, to achieve the same level of annual volume of overland runoff allowable from the development site under pre-development conditions".

In this case, the minimum on-site runoff retention will require the site to retain all runoff from 5 mm storm event through evapotranspiration or rainwater reuse.

The current area measurements and land use types for the site are as follows:

| Land Use | Area (m ²) | Runoff C | Impervious | CN |
|---------------------------|------------------------|----------|------------|----|
| Impervious Roof Area | 2,344.0 | 0.90 | 100% | 98 |
| Soft/Pervious Landscaping | 5,781.7 | 0.25 | 0% | 74 |
| At-Grade Impervious | 10,356.3 | 0.90 | 100% | 98 |
| Green Roof | - | 0.45 | 0% | 98 |
| Total Site Area: | 18,482 | 0.70 | 69% | - |

| Surface Type | Area (m ²) | IA (m) | Volume Abstracted (m ³) | 5 mm Volume (m ³) | Water Balance (m ³) |
|---------------------------|------------------------|--------|-------------------------------------|-------------------------------|---------------------------------|
| Impervious Roof Area | 2,344 | 0.0010 | 2.34 | 11.72 | 9.38 |
| Soft/Pervious Landscaping | 5,782 | 0.0050 | 28.91 | 28.91 | 0.00 |
| At-Grade Impervious | 10,356 | 0.0010 | 10.36 | 51.78 | 41.43 |
| Green Roof | - | 0.0050 | 0.00 | 0.00 | 0.00 |
| Total Site Area: | 18,482 | | 41.61 | 92.41 | 50.80 |

For the purposes of the water balance calculation it is assumed that green roofs can accept 10 mm of rainfall without producing any runoff. This is supported by EPA analysis of green roof manufacturer data sheets (dry unit weights versus saturated unit weights).

It is assumed that the remaining hard surfaces on the site can abstract 1 mm of rainfall, and that all soft landscaped areas can absorb 5 mm

Therefore, volume of runoff during a 5 mm storm event: 50.80 m³

APPENDIX

C

Water Quality Treatments Units



STANDARD OFFLINE Jellyfish Filter Sizing Report

Project Information

| | |
|----------------|---------------------------|
| Date | Friday, December 16, 2022 |
| Project Name | 8 Line and Danby Rd. |
| Project Number | |
| Location | Georgetown |

Jellyfish Filter Design Overview

This report provides information for the sizing and specification of the Jellyfish Filter. When designed properly in accordance to the guidelines detailed in the Jellyfish Filter Technical Manual, the Jellyfish Filter will exceed the performance and longevity of conventional horizontal bed and granular media filters.

Please see www.ImbriumSystems.com for more information.

Jellyfish Filter System Recommendation

The Jellyfish Filter model JF6-6-1 is recommended to meet the water quality objective by treating a flow of 28.6 L/s, which meets or exceeds 90% of the average annual rainfall runoff volume based on 18 years of TORONTO CENTRAL rainfall data for this site. This model has a sediment capacity of 370 kg, which meets or exceeds the estimated average annual sediment load.

| Jellyfish Model | Number of High-Flo Cartridges | Number of Draindown Cartridges | Manhole Diameter (m) | Treatment Flow Rate (L/s) | Sediment Capacity (kg) |
|-----------------|-------------------------------|--------------------------------|----------------------|---------------------------|------------------------|
| JF6-6-1 | 6 | 1 | 1.8 | 28.6 | 370 |

The Jellyfish Filter System

The patented Jellyfish Filter is an engineered stormwater quality treatment technology featuring unique membrane filtration in a compact stand-alone treatment system that removes a high level and wide variety of stormwater pollutants. Exceptional pollutant removal is achieved at high treatment flow rates with minimal head loss and low maintenance costs. Each lightweight Jellyfish Filter cartridge contains an extraordinarily large amount of membrane surface area, resulting in superior flow capacity and pollutant removal capacity.

Maintenance

Regular scheduled inspections and maintenance is necessary to assure proper functioning of the Jellyfish Filter. The maintenance interval is designed to be a minimum of 12 months, but this will vary depending on site loading conditions and upstream pretreatment measures. Quarterly inspections and inspections after all storms beyond the 5-year event are recommended until enough historical performance data has been logged to comfortably initiate an alternative inspection interval.

Please see www.ImbriumSystems.com for more information.

Thank you for the opportunity to present this information to you and your client.

Performance

Jellyfish efficiently captures a high level of Stormwater pollutants, including:


- ☑ 89% of the total suspended solids (TSS) load, including particles less than 5 microns
- ☑ 77% TP removal & 51% TN removal
- ☑ 90% Total Copper, 81% Total Lead, 70% Total Zinc
- ☑ Particulate-bound pollutants such as nutrients, toxic metals, hydrocarbons and bacteria
- ☑ Free oil, Floatable trash and debris

Field Proven Performance

The Jellyfish filter has been field-tested on an urban site with 25 TARP qualifying rain events and field monitored according to the TARP field test protocol, demonstrating:

- A median TSS removal efficiency of 89%, and a median SSC removal of 99%;
- The ability to capture fine particles as indicated by an effluent d50 median of 3 microns for all monitored storm events, and a median effluent turbidity of 5 NTUs;
- A median Total Phosphorus removal of 77%, and a median Total Nitrogen removal of 51%.

Jellyfish Filter Treatment Functions



Pre-treatment and Membrane Filtration

Project Information

| | |
|-----------------|---------------------------|
| Date: | Friday, December 16, 2022 |
| Project Name: | 8 Line and Danby Rd. |
| Project Number: | |
| Location: | Georgetown |

Designer Information

| | |
|----------|-----------------------|
| Company: | WSP Canada Group Ltd. |
| Contact: | Lanxin Zhang |
| Phone #: | |

Notes

| |
|--|
| |
|--|

Design System Requirements

| | | |
|-------------------------|---|----------------|
| Flow Loading | 90% of the Average Annual Runoff based on 18 years of TORONTO CENTRAL rainfall data: | 24 L/s |
| Sediment Loading | Treating 90% of the average annual runoff volume, 5488 m ³ , with a suspended sediment concentration of 60 mg/L. | 329 kg* |

* Indicates that sediment loading is the limiting parameter in the sizing of this Jellyfish system

Recommendation

The Jellyfish Filter model JF6-6-1 is recommended to meet the water quality objective by treating a flow of 28.6 L/s, which meets or exceeds 90% of the average annual rainfall runoff volume based on 18 years of TORONTO CENTRAL rainfall data for this site. This model has a sediment capacity of 370 kg, which meets or exceeds the estimated average annual sediment load.

| Jellyfish Model | Number of High-Flo Cartridges | Number of Draindown Cartridges | Manhole Diameter (m) | Wet Vol Below Deck (L) | Sump Storage (m ³) | Oil Capacity (L) | Treatment Flow Rate (L/s) | Sediment Capacity (kg) |
|-----------------|-------------------------------|--------------------------------|----------------------|------------------------|--------------------------------|------------------|---------------------------|------------------------|
| JF4-1-1 | 1 | 1 | 1.2 | 2313 | 0.34 | 379 | 7.6 | 85 |
| JF4-2-1 | 2 | 1 | 1.2 | 2313 | 0.34 | 379 | 12.6 | 142 |
| JF6-3-1 | 3 | 1 | 1.8 | 5205 | 0.79 | 848 | 17.7 | 199 |
| JF6-4-1 | 4 | 1 | 1.8 | 5205 | 0.79 | 848 | 22.7 | 256 |
| JF6-5-1 | 5 | 1 | 1.8 | 5205 | 0.79 | 848 | 27.8 | 313 |
| JF6-6-1 | 6 | 1 | 1.8 | 5205 | 0.79 | 848 | 28.6 | 370 |
| JF8-6-2 | 6 | 2 | 2.4 | 9252 | 1.42 | 1469 | 35.3 | 398 |
| JF8-7-2 | 7 | 2 | 2.4 | 9252 | 1.42 | 1469 | 40.4 | 455 |
| JF8-8-2 | 8 | 2 | 2.4 | 9252 | 1.42 | 1469 | 45.4 | 512 |
| JF8-9-2 | 9 | 2 | 2.4 | 9252 | 1.42 | 1469 | 50.5 | 569 |
| JF8-10-2 | 10 | 2 | 2.4 | 9252 | 1.42 | 1469 | 50.5 | 626 |
| JF10-11-3 | 11 | 3 | 3.0 | 14456 | 2.21 | 2302 | 63.1 | 711 |
| JF10-12-3 | 12 | 3 | 3.0 | 14456 | 2.21 | 2302 | 68.2 | 768 |
| JF10-12-4 | 12 | 4 | 3.0 | 14456 | 2.21 | 2302 | 70.7 | 796 |
| JF10-13-4 | 13 | 4 | 3.0 | 14456 | 2.21 | 2302 | 75.7 | 853 |
| JF10-14-4 | 14 | 4 | 3.0 | 14456 | 2.21 | 2302 | 78.9 | 910 |
| JF10-15-4 | 15 | 4 | 3.0 | 14456 | 2.21 | 2302 | 78.9 | 967 |
| JF10-16-4 | 16 | 4 | 3.0 | 14456 | 2.21 | 2302 | 78.9 | 1024 |
| JF10-17-4 | 17 | 4 | 3.0 | 14456 | 2.21 | 2302 | 78.9 | 1081 |
| JF10-18-4 | 18 | 4 | 3.0 | 14456 | 2.21 | 2302 | 78.9 | 1138 |
| JF10-19-4 | 19 | 4 | 3.0 | 14456 | 2.21 | 2302 | 78.9 | 1195 |
| JF12-20-5 | 20 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.6 | 1280 |
| JF12-21-5 | 21 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.7 | 1337 |
| JF12-22-5 | 22 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.7 | 1394 |
| JF12-23-5 | 23 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.7 | 1451 |
| JF12-24-5 | 24 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.7 | 1508 |
| JF12-25-5 | 25 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.7 | 1565 |
| JF12-26-5 | 26 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.7 | 1622 |
| JF12-27-5 | 27 | 5 | 3.6 | 20820 | 3.2 | 2771 | 113.7 | 1679 |

Rainfall

| | |
|----------|------------------|
| Name: | TORONTO CENTRAL |
| State: | ON |
| ID: | 100 |
| Record: | 1982 to 1999 |
| Co-ords: | 45°30'N, 90°30'W |

Drainage Area


| | |
|-----------------|-----------|
| Total Area: | 0.9225 ha |
| Imperviousness: | 100% |

Upstream Detention

| | |
|----------------------|-----|
| Peak Release Rate: | n/a |
| Pretreatment Credit: | n/a |

Jellyfish Filter Design Notes

- Typically the Jellyfish Filter is designed in an offline configuration, as all stormwater filter systems will perform for a longer duration between required maintenance services when designed and applied in off-line configurations. Depending on the design parameters, an optional internal bypass may be incorporated into the Jellyfish Filter, however note the inspection and maintenance frequency should be expected to increase above that of an off-line system. Speak to your local representative for more information.



Jellyfish Filter Typical Layout

- Typically, 18 inches (457 mm) of driving head is designed into the system, calculated as the difference in elevation between the top of the diversion structure weir and the invert of the Jellyfish Filter outlet pipe. Alternative driving head values can be designed as 12 to 24 inches (305 to 610mm) depending on specific site requirements, requiring additional sizing and design assistance.
- Typically, the Jellyfish Filter is designed with the inlet pipe configured 6 inches (150 mm) above the outlet invert elevation. However, depending on site parameters this can vary to an optional configuration of the inlet pipe entering the unit below the outlet invert elevation.
- The Jellyfish Filter can accommodate multiple inlet pipes within certain restrictions.
- While the optional inlet below deck configuration offers 0 to 360 degree flexibility between the inlet and outlet pipe, typical systems conform to the following:

| Model Diameter (m) | Minimum Angle Inlet / Outlet Pipes | Minimum Inlet Pipe Diameter (mm) | Minimum Outlet Pipe Diameter (mm) |
|--------------------|------------------------------------|----------------------------------|-----------------------------------|
| 1.2 | 62° | 150 | 200 |
| 1.8 | 59° | 200 | 250 |
| 2.4 | 52° | 250 | 300 |
| 3.0 | 48° | 300 | 450 |
| 3.6 | 40° | 300 | 450 |

- The Jellyfish Filter can be built at all depths of cover generally associated with conventional stormwater conveyance systems. For sites that require minimal depth of cover for the stormwater infrastructure, the Jellyfish Filter can be applied in a shallow application using a hatch cover. The general minimum depth of cover is 36 inches (915 mm) from top of the underslab to outlet invert.
- If driving head calculations account for water elevation during submerged conditions the Jellyfish Filter will function effectively under submerged conditions.
- Jellyfish Filter systems may incorporate grated inlets depending on system configuration.
- For sites with water quality treatment flow rates or mass loadings that exceed the design flow rate of the largest standard Jellyfish Filter manhole models, systems can be designed that hydraulically connect multiple Jellyfish Filters in series or alternatively Jellyfish Vault units can be designed.

STANDARD SPECIFICATION STORMWATER QUALITY – MEMBRANE FILTRATION TREATMENT DEVICE

PART 1 – GENERAL

1.1 WORK INCLUDED

Specifies requirements for construction and performance of an underground stormwater quality membrane filtration treatment device that removes pollutants from stormwater runoff through the unit operations of sedimentation, floatation, and membrane filtration.

1.2 REFERENCE STANDARDS

ASTM C 891: Specification for Installation of Underground Precast Concrete Utility Structures
ASTM C 478: Specification for Precast Reinforced Concrete Manhole Sections
ASTM C 443: Specification for Joints for Concrete Pipe and Manholes, Using Rubber Gaskets
ASTM D 4101: Specification for Copolymer steps construction

CAN/CSA-A257.4-M92

Joints for Circular Concrete Sewer and Culvert Pipe, Manhole Sections and Fittings Using Rubber Gaskets

CAN/CSA-A257.4-M92

Precast Reinforced Circular Concrete Manhole Sections, Catch Basins and Fittings

Canadian Highway Bridge Design Code

1.3 SHOP DRAWINGS

Shop drawings for the structure and performance are to be submitted with each order to the contractor. Contractor shall forward shop drawing submittal to the consulting engineer for approval. Shop drawings are to detail the structure's precast concrete and call out or note the fiberglass (FRP) internals/components.

1.4 PRODUCT SUBSTITUTIONS

No product substitutions shall be accepted unless submitted 10 days prior to project bid date, or as directed by the engineer of record. Submissions for substitutions require review and approval by the Engineer of Record, for hydraulic performance, impact to project designs, equivalent treatment performance, and any required project plan and report (hydrology/hydraulic, water quality, stormwater pollution) modifications that would be required by the approving jurisdictions/agencies. Contractor to coordinate with the Engineer of Record any applicable modifications to the project estimates of cost, bonding amount determinations, plan check fees for changes to approved documents, and/or any other regulatory requirements resulting from the product substitution.

1.5 HANDLING AND STORAGE

Prevent damage to materials during storage and handling.

PART 2 – PRODUCTS

2.1 GENERAL

- 2.1.1 The device shall be a cylindrical or rectangular, all concrete structure (including risers), constructed from precast concrete riser and slab components or monolithic precast structure(s), installed to conform to ASTM C 891 and to any required state highway, municipal or local specifications; whichever is more stringent. The device shall be watertight.
- 2.1.2 Cartridge Deck The cylindrical concrete device shall include a fiberglass deck. The rectangular concrete device shall include a coated aluminum deck. In either instance, the insert shall be bolted and sealed watertight inside the precast concrete chamber. The deck shall serve as: (a) a horizontal divider between the lower treatment zone and the upper treated effluent zone; (b) a deck for attachment of filter cartridges such that the membrane filter elements of each cartridge extend into the lower treatment zone; (c) a platform for maintenance workers to service the filter cartridges (maximum manned weight = 450 pounds (204 kg)); (d) a conduit for conveyance of treated water to the effluent pipe.
- 2.1.3 Membrane Filter Cartridges Filter cartridges shall be comprised of reusable cylindrical membrane filter elements connected to a perforated head plate. The number of membrane filter elements per cartridge shall be a minimum of eleven 2.75-inch (70-mm) diameter elements. The length of each filter element shall be a minimum 15 inches (381 mm). Each cartridge shall be fitted into the cartridge deck by insertion into a cartridge receptacle that is permanently mounted into the cartridge deck. Each cartridge shall be secured by a cartridge lid that is threaded onto the receptacle, or similar mechanism to secure the cartridge into the deck. The maximum treatment flow rate of a filter cartridge shall be controlled by an orifice in the cartridge lid, or on the individual cartridge itself, and based on a design flux rate (surface loading rate) determined by the maximum treatment flow rate per unit of filtration membrane surface area. The maximum design flux rate shall be 0.21 gpm/ft² (0.142 lps/m²).

Each membrane filter cartridge shall allow for manual installation and removal. Each filter cartridge shall have filtration membrane surface area and dry installation weight as follows (if length of filter cartridge is between those listed below, the surface area and weight shall be proportionate to the next length shorter and next length longer as shown below):

| Filter Cartridge Length (in / mm) | Minimum Filtration Membrane Surface Area (ft ² / m ²) | Maximum Filter Cartridge Dry Weight (lbs / kg) |
|-----------------------------------|--|--|
| 15 | 106 / 9.8 | 10.5 / 4.8 |
| 27 | 190 / 17.7 | 15.0 / 6.8 |
| 40 | 282 / 26.2 | 20.5 / 9.3 |
| 54 | 381 / 35.4 | 25.5 / 11.6 |

- 2.1.4 Backwashing Cartridges The filter device shall have a weir extending above the cartridge deck, or other mechanism, that encloses the high flow rate filter cartridges when placed in their respective cartridge receptacles within the cartridge deck. The weir, or other mechanism, shall collect a pool of filtered water during inflow events that backwashes the high flow rate cartridges when the inflow

event subsides. All filter cartridges and membranes shall be reusable and allow for the use of filtration membrane rinsing procedures to restore flow capacity and sediment capacity; extending cartridge service life.

- 2.1.5 Maintenance Access to Captured Pollutants The filter device shall contain an opening(s) that provides maintenance access for removal of accumulated floatable pollutants and sediment, removal of and replacement of filter cartridges, cleaning of the sump, and rinsing of the deck. Access shall have a minimum clear vertical clear space over all of the filter cartridges. Filter cartridges shall be able to be lifted straight vertically out of the receptacles and deck for the entire length of the cartridge.
- 2.1.6 Bend Structure The device shall be able to be used as a bend structure with minimum angles between inlet and outlet pipes of 90-degrees or less in the stormwater conveyance system.
- 2.1.7 Double-Wall Containment of Hydrocarbons The cylindrical precast concrete device shall provide double-wall containment for hydrocarbon spill capture by a combined means of an inner wall of fiberglass, to a minimum depth of 12 inches (305 mm) below the cartridge deck, and the precast vessel wall.
- 2.1.8 Baffle The filter device shall provide a baffle that extends from the underside of the cartridge deck to a minimum length equal to the length of the membrane filter elements. The baffle shall serve to protect the membrane filter elements from contamination by floatables and coarse sediment. The baffle shall be flexible and continuous in cylindrical configurations, and shall be a straight concrete or aluminum wall in rectangular configurations.
- 2.1.9 Sump The device shall include a minimum 24 inches (610 mm) of sump below the bottom of the cartridges for sediment accumulation, unless otherwise specified by the design engineer. Depths less than 24 inches may have an impact on the total performance and/or longevity between cartridge maintenance/replacement of the device.

2.2 PRECAST CONCRETE SECTIONS

All precast concrete components shall be manufactured to a minimum live load of HS-20 truck loading or greater based on local regulatory specifications, unless otherwise modified or specified by the design engineer, and shall be watertight.

2.3 JOINTS All precast concrete manhole configuration joints shall use nitrile rubber gaskets and shall meet the requirements of ASTM C443, Specification C1619, Class D or engineer approved equal to ensure oil resistance. Mastic sealants or butyl tape are not an acceptable alternative.

2.4 GASKETS Only profile neoprene or nitrile rubber gaskets in accordance to CSA A257.3-M92 will be accepted. Mastic sealants, butyl tape or Con Seal CS-101 are not acceptable gasket materials.

2.5 FRAME AND COVER Frame and covers must be manufactured from cast-iron or other composite material tested to withstand H-20 or greater design loads, and as approved by the

local regulatory body. Frames and covers must be embossed with the name of the device manufacturer or the device brand name.

- 2.6 DOORS AND HATCHES If provided shall meet designated loading requirements or at a minimum for incidental vehicular traffic.
- 2.7 CONCRETE All concrete components shall be manufactured according to local specifications and shall meet the requirements of ASTM C 478.
- 2.8 FIBERGLASS The fiberglass portion of the filter device shall be constructed in accordance with the following standard: ASTM D-4097: Contact Molded Glass Fiber Reinforced Chemical Resistant Tanks.
- 2.9 STEPS Steps shall be constructed according to ASTM D4101 of copolymer polypropylene, and be driven into preformed or pre-drilled holes after the concrete has cured, installed to conform to applicable sections of state, provincial and municipal building codes, highway, municipal or local specifications for the construction of such devices.
- 2.10 INSPECTION All precast concrete sections shall be inspected to ensure that dimensions, appearance and quality of the product meet local municipal specifications and ASTM C 478.

PART 3 – PERFORMANCE

3.1 GENERAL

- 3.1.1 Verification – The stormwater quality filter must be verified in accordance with ISO 14034:2016 Environmental management – Environmental technology verification (ETV).
- 3.1.2 Function - The stormwater quality filter treatment device shall function to remove pollutants by the following unit treatment processes; sedimentation, floatation, and membrane filtration.
- 3.1.3 Pollutants - The stormwater quality filter treatment device shall remove oil, debris, trash, coarse and fine particulates, particulate-bound pollutants, metals and nutrients from stormwater during runoff events.
- 3.1.4 Bypass - The stormwater quality filter treatment device shall typically utilize an external bypass to divert excessive flows. Internal bypass systems shall be equipped with a floatables baffle, and must avoid passage through the sump and/or cartridge filtration zone.
- 3.1.5 Treatment Flux Rate (Surface Loading Rate) – The stormwater quality filter treatment device shall treat 100% of the required water quality treatment flow based on a maximum design treatment flux rate (surface loading rate) across the membrane filter cartridges of 0.21 gpm/ft² (0.142 lps/m²).

3.2 FIELD TEST PERFORMANCE

At a minimum, the stormwater quality filter device shall have been field tested and verified with a minimum 25 TARP qualifying storm events and field monitoring shall have been conducted according to the TARP 2009 NJDEP TARP field test protocol, and have received NJCAT verification.

- 3.2.1 Suspended Solids Removal - The stormwater quality filter treatment device shall have demonstrated a minimum median TSS removal efficiency of 85% and a minimum median SSC removal efficiency of 95%.
- 3.2.2 Runoff Volume – The stormwater quality filter treatment device shall be engineered, designed, and sized to treat a minimum of 90 percent of the annual runoff volume determined from use of a minimum 15-year rainfall data set.
- 3.2.3 Fine Particle Removal - The stormwater quality filter treatment device shall have demonstrated the ability to capture fine particles as indicated by a minimum median removal efficiency of 75% for the particle fraction less than 25 microns, an effluent d_{50} of 15 microns or lower for all monitored storm events.
- 3.2.4 Turbidity Reduction - The stormwater quality filter treatment device shall have demonstrated the ability to reduce the turbidity from influent from a range of 5 to 171 NTU to an effluent turbidity of 15 NTU or lower.
- 3.2.5 Nutrient (Total Phosphorus & Total Nitrogen) Removal - The stormwater quality filter treatment device shall have demonstrated a minimum median Total Phosphorus removal of 55%, and a minimum median Total Nitrogen removal of 50%.
- 3.2.6 Metals (Total Zinc & Total Copper) Removal - The stormwater quality filter treatment device shall have demonstrated a minimum median Total Zinc removal of 55%, and a minimum median Total Copper removal of 85%.

3.3 INSPECTION and MAINTENANCE

The stormwater quality filter device shall have the following features:

- 3.3.1 Durability of membranes are subject to good handling practices during inspection and maintenance (removal, rinsing, and reinsertion) events, and site specific conditions that may have heavier or lighter loading onto the cartridges, and pollutant variability that may impact the membrane structural integrity. Membrane maintenance and replacement shall be in accordance with manufacturer's recommendations.
- 3.3.2 Inspection which includes trash and floatables collection, sediment depth determination, and visible determination of backwash pool depth shall be easily conducted from grade (outside the structure).
- 3.3.3 Manual rinsing of the reusable filter cartridges shall promote restoration of the flow capacity and sediment capacity of the filter cartridges, extending cartridge service life.

- 3.3.4 The filter device shall have a minimum 12 inches (305 mm) of sediment storage depth, and a minimum of 12 inches between the top of the sediment storage and bottom of the filter cartridge tentacles, unless otherwise specified by the design engineer. Variances may have an impact on the total performance and/or longevity between cartridge maintenance/replacement of the device.
- 3.3.5 Sediment removal from the filter treatment device shall be able to be conducted using a standard maintenance truck and vacuum apparatus, and a minimum one point of entry to the sump that is unobstructed by filter cartridges.
- 3.3.6 Maintenance access shall have a minimum clear height that provides suitable vertical clear space over all of the filter cartridges. Filter cartridges shall be able to be lifted straight vertically out of the receptacles and deck for the entire length of the cartridge.
- 3.3.7 Filter cartridges shall be able to be maintained without the requirement of additional lifting equipment.

PART 4 – EXECUTION

4.1 INSTALLATION

4.1.1 PRECAST DEVICE CONSTRUCTION SEQUENCE

The installation of a watertight precast concrete device should conform to ASTM C 891 and to any state highway, municipal or local specifications for the construction of manholes, whichever is more stringent. Selected sections of a general specification that are applicable are summarized below.

- 4.1.1.1 The watertight precast concrete device is installed in sections in the following sequence:
 - aggregate base
 - base slab
 - treatment chamber and cartridge deck riser section(s)
 - bypass section
 - connect inlet and outlet pipes
 - concrete riser section(s) and/or transition slab (if required)
 - maintenance riser section(s) (if required)
 - frame and access cover

4.1.2 The precast base should be placed level at the specified grade. The entire base should be in contact with the underlying compacted granular material. Subsequent sections, complete with joint seals, should be installed in accordance with the precast concrete manufacturer's recommendations.

4.1.3 Adjustment of the stormwater quality treatment device can be performed by lifting the upper sections free of the excavated area, re-leveling the base, and re-installing the sections. Damaged sections and gaskets should be repaired or replaced as necessary to restore original condition and watertight seals. Once the stormwater quality treatment device has been constructed, any/all lift holes must be plugged watertight with mortar or non-shrink grout.

4.1.4 Inlet and Outlet Pipes Inlet and outlet pipes should be securely set into the device using approved pipe seals (flexible boot connections, where applicable) so that the structure is watertight, and such that any pipe intrusion into the device does not impact the device functionality.

4.1.5 Frame and Cover Installation Adjustment units (e.g. grade rings) should be installed to set the frame and cover at the required elevation. The adjustment units should be laid in a full bed of mortar with successive units being joined using sealant recommended by the manufacturer. Frames for the cover should be set in a full bed of mortar at the elevation specified.

4.2 MAINTENANCE ACCESS WALL

In some instances the Maintenance Access Wall, if provided, shall require an extension attachment and sealing to the precast wall and cartridge deck at the job site, rather than at the precast facility. In this instance, installation of these components shall be performed according to instructions provided by the manufacturer.

4.3 FILTER CARTRIDGE INSTALLATION Filter cartridges shall be installed in the cartridge deck only after the construction site is fully stabilized and in accordance with the manufacturer's guidelines and recommendations. Contractor to contact the manufacturer to schedule cartridge delivery and review procedures/requirements to be completed to the device prior to installation of the cartridges and activation of the system.

PART 5 – QUALITY ASSURANCE

5.1 FILTER CARTRIDGE INSTALLATION Manufacturer shall coordinate delivery of filter cartridges and other internal components with contractor. Filter cartridges shall be delivered and installed complete after site is stabilized and unit is ready to accept cartridges. Unit is ready to accept cartridges after it has been cleaned out and any standing water, debris, and other materials have been removed. Contractor shall take appropriate action to protect the filter cartridge receptacles and filter cartridges from damage during construction, and in accordance with the manufacturer's recommendations and guidance. For systems with cartridges installed prior to full site stabilization and prior to system activation, the contractor can plug inlet and outlet pipes to prevent stormwater and other influent from entering the device. Plugs must be removed during the activation process.

5.2 INSPECTION AND MAINTENANCE

5.2.1 The manufacturer shall provide an Owner's Manual upon request.

5.2.2 After construction and installation, and during operation, the device shall be inspected and cleaned as necessary based on the manufacturer's recommended inspection and maintenance guidelines and the local regulatory agency/body.

5.3 REPLACEMENT FILTER CARTRIDGES When replacement membrane filter elements and/or other parts are required, only membrane filter elements and parts approved by the manufacturer for use with the stormwater quality filter device shall be installed.

END OF SECTION

STANDARD PERFORMANCE SPECIFICATION STORMWATER QUALITY – MEMBRANE FILTRATION TREATMENT DEVICE

PART 1 – GENERAL

1.1 WORK INCLUDED

This section specifies requirements for selecting, sizing, and designing an underground stormwater quality membrane filtration treatment device that removes pollutants from stormwater runoff through the unit operations of sedimentation, floatation, and membrane filtration.

1.2 REFERENCE STANDARDS & PROCEDURES

ISO 14034:2016 Environmental Management – Environmental Technology Verification (ETV)

1.3 SUBMITTALS

- 1.3.1 All submittals, including sizing reports & shop drawings, shall be submitted upon request with each order to the contractor then forwarded to the Engineer of Record for review and acceptance. Shop drawings shall detail all OGS components, elevations, and sequence of construction.
- 1.3.2 Alternative devices shall have features identical to or greater than the specified device, including: filtration surface area, treatment chamber diameter, treatment chamber wet volume, sediment storage volume, and oil storage volume.
- 1.3.3 Unless directed otherwise by the Engineer of Record, filtration treatment device product substitutions or alternatives submitted within ten days prior to project bid shall not be accepted. All alternatives or substitutions submitted shall be signed and sealed by a local registered Professional Engineer, based on the exact same criteria detailed in Section 3, in entirety, subject to review and approval by the Engineer of Record.

PART 2 – PRODUCTS

2.1 GENERAL

- 2.1.1 Maintenance Access to Captured Pollutants The filter device shall contain an opening(s) that provides maintenance access for removal of accumulated floatable pollutants and sediment, removal of and replacement of filter cartridges, cleaning of the sump, and rinsing of the internal components. Access shall have a minimum clear vertical clear space over all of the filter cartridges. Filter cartridges shall be able to be lifted straight vertically out of their installed placement for the entire length of the cartridge.
- 2.1.2 Pollutant Storage: The Filter device shall include a sump for sediment storage, and a protected volume for the capture and storage of petroleum hydrocarbons and buoyant gross pollutants.

PART 3 – PERFORMANCE

3.1 GENERAL

- 3.1.1 Verification – The stormwater quality filter treatment device shall have been field tested in accordance with either TARP Tier II Protocol (TARP, 2003) and New Jersey Tier II Stormwater Test Requirements – Amendments to TARP Tier II Protocol (NJDEP, 2009) or Washington State Technology Assessment Protocol – Ecology (TAPE), 2011 or later version. The field test shall have been verified in accordance with ISO 14034:2016 Environmental Management – Environmental Technology Verification (ETV). See Section 3.2 of this specification for field test performance requirements.

3.2 FIELD TEST PERFORMANCE

The field test (as specified in section 3.1.1) shall have monitored a minimum of twenty (20) TARP or TAPE qualifying storm events, and report at **minimum** the following results:

- 3.2.1 Suspended Solids Removal - The stormwater quality filter treatment device shall have ISO 14034 ETV verified load based median TSS removal efficiency of at least 85% and load based median SSC removal efficiency of at least 98%.
- 3.2.2 Runoff Volume – The stormwater quality filter treatment device shall be engineered, designed, and sized to treat a minimum of 90 percent of the annual runoff volume determined from use of a minimum 15-year rainfall data set.
- 3.2.3 Fine Particle Removal - The stormwater quality filter treatment device shall have demonstrated the ability to capture fine particles as indicated by a minimum median removal efficiency of 75% for the particle fraction less than 25 microns, and an effluent d_{50} of 15 microns or lower for all monitored storm events.
- 3.2.4 Turbidity Reduction - The stormwater quality filter treatment device shall have demonstrated the ability to reduce turbidity such that effluent turbidity is 15 NTU or lower.
- 3.2.5 Nutrients & Metals – The stormwater quality filter treatment device shall have ISO 14034 ETV Verified minimum load based removal efficiencies for the following:
- 3.2.5.1 Total Phosphorus (TP) Removal - Median TP removal efficiency of at least 49%.
- 3.2.5.2 Total Nitrogen (TN) Removal - Median TN removal efficiency of at least 39%.
- 3.2.5.3 Total Zinc (Zn) Removal - Median Zn removal efficiency of at least 69%.
- 3.2.5.4 Total Copper (Cu) Removal - Median Cu removal efficiency of at least 91%.

END OF SECTION


APPENDIX

D

Hydrological Model Output
(HydroCAD)

Area Listing (all nodes)

| Area (sq-meters) | C | Description (subcatchment-numbers) |
|---------------------|-------------|---------------------------------------|
| 10,356.0 | 0.90 | At-Grade Impervious (1S) |
| 2,344.0 | 0.90 | Impervious Roof Area (1S) |
| 5,782.0 | 0.25 | Landscaping (1S) |
| 18,482.0 | 0.70 | TOTAL AREA |



Soil Listing (all nodes)

| Area (sq-meters) | Soil Group | Subcatchment Numbers |
|---------------------|---------------|-------------------------|
| 0.0 | HSG A | |
| 0.0 | HSG B | |
| 0.0 | HSG C | |
| 0.0 | HSG D | |
| 18,482.0 | Other | 1S |
| 18,482.0 | | TOTAL AREA |

Ground Covers (all nodes)

| HSG-A (sq-meters) | HSG-B (sq-meters) | HSG-C (sq-meters) | HSG-D (sq-meters) | Other (sq-meters) | Total (sq-meters) | Ground Cover |
|----------------------|----------------------|----------------------|----------------------|----------------------|----------------------|------------------------|
| 0.0 | 0.0 | 0.0 | 0.0 | 10,356.0 | 10,356.0 | At-Grade Impervious |
| 0.0 | 0.0 | 0.0 | 0.0 | 2,344.0 | 2,344.0 | Roof Area |
| 0.0 | 0.0 | 0.0 | 0.0 | 5,782.0 | 5,782.0 | Landscaping |
| 0.0 | 0.0 | 0.0 | 0.0 | 18,482.0 | 18,482.0 | TOTAL AREA |

Time span=0.00-9.00 hrs, dt=0.01 hrs, 901 points
 Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Controlled Site Area Runoff Area=18,482.0 m² 0.00% Impervious Runoff Depth=12 mm
 Tc=10.0 min C=0.70 Runoff=0.1588 m³/s 228.7 m³

Pond 2P: Cistern Storage Peak Elev=0.578 m Storage=156.0 m³ Inflow=0.1588 m³/s 228.7 m³
 Outflow=0.1225 m³/s 227.9 m³

Total Runoff Area = 18,482.0 m² Runoff Volume = 228.7 m³ Average Runoff Depth = 12 mm
100.00% Pervious = 18,482.0 m² 0.00% Impervious = 0.0 m²

Summary for Subcatchment 1S: Controlled Site Area


Runoff = 0.1588 m³/s @ 0.17 hrs, Volume= 228.7 m³, Depth= 12 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Halton Hills 2-Year Duration=24 min, Inten=44.2 mm/hr

| Area (m ²) | C | Description |
|------------------------|------|-----------------------|
| 10,356.0 | 0.90 | At-Grade Impervious |
| 2,344.0 | 0.90 | Impervious Roof Area |
| 5,782.0 | 0.25 | Landscaping |
| 18,482.0 | 0.70 | Weighted Average |
| 18,482.0 | | 100.00% Pervious Area |

| Tc (min) | Length (meters) | Slope (m/m) | Velocity (m/sec) | Capacity (m ³ /s) | Description |
|----------|-----------------|-------------|------------------|------------------------------|---------------|
| 10.0 | | | | | Direct Entry, |

Subcatchment 1S: Controlled Site Area



Summary for Pond 2P: Cistern Storage

Inflow Area = 18,482.0 m², 0.00% Impervious, Inflow Depth = 12 mm for 2-Year event
 Inflow = 0.1588 m³/s @ 0.17 hrs, Volume= 228.7 m³
 Outflow = 0.1225 m³/s @ 0.44 hrs, Volume= 227.9 m³, Atten= 23%, Lag= 16.1 min
 Primary = 0.1225 m³/s @ 0.44 hrs, Volume= 227.9 m³

Routing by Stor-Ind method, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Starting Elev= 0.200 m Surf.Area= 270.0 m² Storage= 54.0 m³
 Peak Elev= 0.578 m @ 0.44 hrs Surf.Area= 270.0 m² Storage= 156.0 m³ (102.0 m³ above start)


Plug-Flow detention time= 29.8 min calculated for 173.9 m³ (76% of inflow)
 Center-of-Mass det. time= 19.9 min (36.9 - 17.0)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|----------------------|--|
| #1 | 0.000 m | 378.0 m ³ | 1.00 mW x 270.00 mL x 1.40 mH Prismatoid |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 0.200 m | 300 mm Vert. Orifice/Grate Tube C= 0.820 |

Primary OutFlow Max=0.1225 m³/s @ 0.44 hrs HW=0.578 m (Free Discharge)
 1=Orifice/Grate Tube (Orifice Controls 0.1225 m³/s @ 1.73 m/s)

Pond 2P: Cistern Storage



Time span=0.00-9.00 hrs, dt=0.01 hrs, 901 points
 Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Controlled Site Area Runoff Area=18,482.0 m² 0.00% Impervious Runoff Depth=18 mm
 Tc=10.0 min C=0.70 Runoff=0.2272 m³/s 327.2 m³

Pond 2P: Cistern Storage Peak Elev=0.755 m Storage=203.8 m³ Inflow=0.2272 m³/s 327.2 m³
 Outflow=0.1634 m³/s 326.3 m³

Total Runoff Area = 18,482.0 m² Runoff Volume = 327.2 m³ Average Runoff Depth = 18 mm
100.00% Pervious = 18,482.0 m² 0.00% Impervious = 0.0 m²

Summary for Subcatchment 1S: Controlled Site Area


Runoff = 0.2272 m³/s @ 0.17 hrs, Volume= 327.2 m³, Depth= 18 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Halton Hills 5-Year Duration=24 min, Inten=63.2 mm/hr

| Area (m²) | C | Description |
|-----------|------|-----------------------|
| 10,356.0 | 0.90 | At-Grade Impervious |
| 2,344.0 | 0.90 | Impervious Roof Area |
| 5,782.0 | 0.25 | Landscaping |
| 18,482.0 | 0.70 | Weighted Average |
| 18,482.0 | | 100.00% Pervious Area |

| Tc (min) | Length (meters) | Slope (m/m) | Velocity (m/sec) | Capacity (m³/s) | Description |
|----------|-----------------|-------------|------------------|-----------------|---------------|
| 10.0 | | | | | Direct Entry, |

Subcatchment 1S: Controlled Site Area



Summary for Pond 2P: Cistern Storage

Inflow Area = 18,482.0 m², 0.00% Impervious, Inflow Depth = 18 mm for 5-Year event
 Inflow = 0.2272 m³/s @ 0.17 hrs, Volume= 327.2 m³
 Outflow = 0.1634 m³/s @ 0.45 hrs, Volume= 326.3 m³, Atten= 28%, Lag= 16.6 min
 Primary = 0.1634 m³/s @ 0.45 hrs, Volume= 326.3 m³

Routing by Stor-Ind method, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Starting Elev= 0.200 m Surf.Area= 270.0 m² Storage= 54.0 m³
 Peak Elev= 0.755 m @ 0.45 hrs Surf.Area= 270.0 m² Storage= 203.8 m³ (149.8 m³ above start)


Plug-Flow detention time= 25.2 min calculated for 272.3 m³ (83% of inflow)
 Center-of-Mass det. time= 18.5 min (35.5 - 17.0)

| Volume | Invert | Avail.Storage | Storage | Description |
|--------|---------|---------------|------------------------------|-------------|
| #1 | 0.000 m | 378.0 m³ | 1.00 mW x 270.0 mL x 1.40 mH | Prismatoid |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 0.200 m | 300 mm Vert. Orifice/Grate Tube C= 0.820 |

Primary OutFlow Max=0.1633 m³/s @ 0.45 hrs HW=0.755 m (Free Discharge)
 1=Orifice/Grate Tube (Orifice Controls 0.1633 m³/s @ 2.31 m/s)

Pond 2P: Cistern Storage



Time span=0.00-9.00 hrs, dt=0.01 hrs, 901 points
 Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Controlled Site Area Runoff Area=18,482.0 m² 0.00% Impervious Runoff Depth=21 mm
 Tc=10.0 min C=0.70 Runoff=0.2691 m³/s 387.5 m³

Pond 2P: Cistern Storage Peak Elev=0.874 m Storage=236.0 m³ Inflow=0.2691 m³/s 387.5 m³
 Outflow=0.1858 m³/s 386.6 m³

Total Runoff Area = 18,482.0 m² Runoff Volume = 387.5 m³ Average Runoff Depth = 21 mm
100.00% Pervious = 18,482.0 m² 0.00% Impervious = 0.0 m²

Summary for Subcatchment 1S: Controlled Site Area


Runoff = 0.2691 m³/s @ 0.17 hrs, Volume= 387.5 m³, Depth= 21 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Halton Hills 10-Year Duration=24 min, Inten=74.9 mm/hr

| Area (m²) | C | Description |
|-----------|------|-----------------------|
| 10,356.0 | 0.90 | At-Grade Impervious |
| 2,344.0 | 0.90 | Impervious Roof Area |
| 5,782.0 | 0.25 | Landscaping |
| 18,482.0 | 0.70 | Weighted Average |
| 18,482.0 | | 100.00% Pervious Area |

| Tc (min) | Length (meters) | Slope (m/m) | Velocity (m/sec) | Capacity (m³/s) | Description |
|----------|-----------------|-------------|------------------|-----------------|---------------|
| 10.0 | | | | | Direct Entry, |

Subcatchment 1S: Controlled Site Area



Summary for Pond 2P: Cistern Storage

Inflow Area = 18,482.0 m², 0.00% Impervious, Inflow Depth = 21 mm for 10-Year event
 Inflow = 0.2691 m³/s @ 0.17 hrs, Volume= 387.5 m³
 Outflow = 0.1858 m³/s @ 0.45 hrs, Volume= 386.6 m³, Atten= 31%, Lag= 16.9 min
 Primary = 0.1858 m³/s @ 0.45 hrs, Volume= 386.6 m³

Routing by Stor-Ind method, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Starting Elev= 0.200 m Surf.Area= 270.0 m² Storage= 54.0 m³
 Peak Elev= 0.874 m @ 0.45 hrs Surf.Area= 270.0 m² Storage= 236.0 m³ (182.0 m³ above start)


Plug-Flow detention time= 24.0 min calculated for 332.6 m³ (86% of inflow)
 Center-of-Mass det. time= 18.3 min (35.3 - 17.0)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|----------------------|--|
| #1 | 0.000 m | 378.0 m ³ | 1.00 mW x 270.00 mL x 1.40 mH Prismatoid |

| Device | Routing | Invert | Outlet Devices | C |
|--------|---------|---------|---------------------------------|-------|
| #1 | Primary | 0.200 m | 300 mm Vert. Orifice/Grate Tube | 0.820 |

Primary OutFlow Max=0.1858 m³/s @ 0.45 hrs HW=0.874 m (Free Discharge)
 1=Orifice/Grate Tube (Orifice Controls 0.1858 m³/s @ 2.63 m/s)

Pond 2P: Cistern Storage



Summary for Subcatchment 1S: Controlled Site Area


Runoff = 0.3194 m³/s @ 0.17 hrs, Volume= 460.0 m³, Depth= 25 mm

Routing by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Halton Hills 25-Year Duration=24 min, Inten=88.9 mm/hr

| Area (m ²) | C | Description |
|------------------------|---------|----------------------|
| 10,356.0 | 0.90 | At-Grade Impervious |
| 2,344.0 | 0.90 | Impervious Roof Area |
| 5,782.0 | 0.25 | Landscaping |
| 18,482.0 | 0.70 | Weighted Average |
| 18,482.0 | 100.00% | Pervious Area |

| Tc (min) | Length (meters) | Slope (m/m) | Velocity (m/sec) | Capacity (m ³ /s) | Description |
|----------|-----------------|-------------|------------------|------------------------------|---------------|
| 10.0 | | | | | Direct Entry, |

Subcatchment 1S: Controlled Site Area



Time span=0.00-9.00 hrs, dt=0.01 hrs, 901 points
 Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment1S: Controlled Site Area Runoff Area=18,482.0 m² 0.00% Impervious Runoff Depth=25 mm
 Tc=10.0 min C=0.70 Runoff=0.3194 m³/s 460.0 m³

Pond 2P: Cistern Storage Peak Elev=1.025 m Storage=276.7 m³ Inflow=0.3194 m³/s 460.0 m³
 Outflow=0.2109 m³/s 459.1 m³

Total Runoff Area = 18,482.0 m² Runoff Volume = 460.0 m³ Average Runoff Depth = 25 mm
 100.00% Pervious = 18,482.0 m² 0.00% Impervious = 0.0 m²

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|----------------------|--|
| #1 | 0.000 m | 378.0 m ³ | 1.00 mW x 270.00 mL x 1.40 mH Prismatoid |

| Device | Routing | Invert | Outlet Devices | C |
|--------|---------|---------|---------------------------------|-------|
| #1 | Primary | 0.200 m | 300 mm Vert. Orifice/Grate Tube | 0.820 |

Primary OutFlow Max=0.2109 m³/s @ 0.46 hrs HW=1.025 m (Free Discharge)
 1=Orifice/Grate Tube (Orifice Controls 0.2109 m³/s @ 2.98 m/s)

Pond 2P: Cistern Storage



Summary for Pond 2P: Cistern Storage

Inflow Area = 18,482.0 m², 0.00% Impervious, Inflow Depth = 25 mm for 25-Year event
 Inflow = 0.3194 m³/s @ 0.17 hrs, Volume= 460.0 m³
 Outflow = 0.2109 m³/s @ 0.46 hrs, Volume= 459.1 m³, Atten= 34%, Lag= 17.2 min
 Primary = 0.2109 m³/s @ 0.46 hrs, Volume= 459.1 m³

Routing by Stor-Ind method, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Starting Elev= 0.200 m Surf.Area= 270.0 m² Storage= 54.0 m³
 Peak Elev= 1.025 m @ 0.46 hrs Surf.Area= 270.0 m² Storage= 276.7 m³ (222.7 m³ above start)


Plug-Flow detention time= 22.8 min calculated for 404.6 m³ (88% of inflow)
 Center-of-Mass det. time= 18.4 min (35.4 - 17.0)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|----------------------|--|
| #1 | 0.000 m | 378.0 m ³ | 1.00 mW x 270.00 mL x 1.40 mH Prismatoid |

| Device | Routing | Invert | Outlet Devices | C |
|--------|---------|---------|---------------------------------|-------|
| #1 | Primary | 0.200 m | 300 mm Vert. Orifice/Grate Tube | 0.820 |

Primary OutFlow Max=0.2109 m³/s @ 0.46 hrs HW=1.025 m (Free Discharge)
 1=Orifice/Grate Tube (Orifice Controls 0.2109 m³/s @ 2.98 m/s)

Pond 2P: Cistern Storage



Time span=0.00-9.00 hrs, dt=0.01 hrs, 901 points
 Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Controlled Site Area Runoff Area=18,482.0 m² 0.00% Impervious Runoff Depth=28 mm
 Tc=10.0 min C=0.70 Runoff=0.3593 m³/s 517.4 m³

Pond 2P: Cistern Storage Peak Elev=1.150 m Storage=310.5 m³ Inflow=0.3593 m³/s 517.4 m³
 Outflow=0.2296 m³/s 516.5 m³

Total Runoff Area = 18,482.0 m² Runoff Volume = 517.4 m³ Average Runoff Depth = 28 mm
100.00% Pervious = 18,482.0 m² 0.00% Impervious = 0.0 m²

Summary for Subcatchment 1S: Controlled Site Area


Runoff = 0.3593 m³/s @ 0.17 hrs, Volume= 517.4 m³, Depth= 28 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Halton Hills 50-Year Duration=24 min, Inten=100.0 mm/hr

| Area (m ²) | C | Description |
|------------------------|------|-----------------------|
| 10,356.0 | 0.90 | At-Grade Impervious |
| 2,344.0 | 0.90 | Impervious Roof Area |
| 5,782.0 | 0.25 | Landscaping |
| 18,482.0 | 0.70 | Weighted Average |
| 18,482.0 | | 100.00% Pervious Area |

| Tc (min) | Length (meters) | Slope (m/m) | Velocity (m/sec) | Capacity (m ³ /s) | Description |
|----------|-----------------|-------------|------------------|------------------------------|---------------|
| 10.0 | | | | | Direct Entry, |

Subcatchment 1S: Controlled Site Area



Summary for Pond 2P: Cistern Storage

Inflow Area = 18,482.0 m², 0.00% Impervious, Inflow Depth = 28 mm for 50-Year event
 Inflow = 0.3593 m³/s @ 0.17 hrs, Volume= 517.4 m³
 Outflow = 0.2296 m³/s @ 0.46 hrs, Volume= 516.5 m³, Atten= 36%, Lag= 17.4 min
 Primary = 0.2296 m³/s @ 0.46 hrs, Volume= 516.5 m³

Routing by Stor-Ind method, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Starting Elev= 0.200 m Surf.Area= 270.0 m² Storage= 54.0 m³
 Peak Elev= 1.150 m @ 0.46 hrs Surf.Area= 270.0 m² Storage= 310.5 m³ (256.5 m³ above start)


Plug-Flow detention time= 22.5 min calculated for 462.0 m³ (89% of inflow)
 Center-of-Mass det. time= 18.6 min (35.6 - 17.0)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|----------------------|---|
| #1 | 0.000 m | 378.0 m ³ | 1.00 mW x 270.00 mL x 1.40 mH Prismatic |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 0.200 m | 300 mm Vert. Orifice/Grate Tube C= 0.820 |

Primary OutFlow Max=0.2296 m³/s @ 0.46 hrs HW=1.150 m (Free Discharge)
 1=Orifice/Grate Tube (Orifice Controls 0.2296 m³/s @ 3.25 m/s)

Pond 2P: Cistern Storage



Time span=0.00-9.00 hrs, dt=0.01 hrs, 901 points
 Runoff by Rational method, Rise/Fall=1.0/1.0 xTc
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment 1S: Controlled Site Area Runoff Area=18,482.0 m² 0.00% Impervious Runoff Depth=31 mm
 Tc=10.0 min C=0.70 Runoff=0.3963 m³/s 570.7 m³

Pond 2P: Cistern Storage Peak Elev=1.270 m Storage=342.8 m³ Inflow=0.3963 m³/s 570.7 m³
 Outflow=0.2462 m³/s 569.8 m³

Total Runoff Area = 18,482.0 m² Runoff Volume = 570.7 m³ Average Runoff Depth = 31 mm
100.00% Pervious = 18,482.0 m² 0.00% Impervious = 0.0 m²

Summary for Subcatchment 1S: Controlled Site Area


Runoff = 0.3963 m³/s @ 0.17 hrs, Volume= 570.7 m³, Depth= 31 mm

Runoff by Rational method, Rise/Fall=1.0/1.0 xTc, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Halton Hills 100-Year Duration=24 min, Inten=110.3 mm/hr

| Area (m²) | C | Description |
|-----------|------|-----------------------|
| 10,356.0 | 0.90 | At-Grade Impervious |
| 2,344.0 | 0.90 | Impervious Roof Area |
| 5,782.0 | 0.25 | Landscaping |
| 18,482.0 | 0.70 | Weighted Average |
| 18,482.0 | | 100.00% Pervious Area |

| Tc (min) | Length (meters) | Slope (m/m) | Velocity (m/sec) | Capacity (m³/s) | Description |
|----------|-----------------|-------------|------------------|-----------------|---------------|
| 10.0 | | | | | Direct Entry, |

Subcatchment 1S: Controlled Site Area



Summary for Pond 2P: Cistern Storage

Inflow Area = 18,482.0 m², 0.00% Impervious, Inflow Depth = 31 mm for 100-Year event
 Inflow = 0.3963 m³/s @ 0.17 hrs, Volume= 570.7 m³
 Outflow = 0.2462 m³/s @ 0.46 hrs, Volume= 569.8 m³, Atten= 38%, Lag= 17.6 min
 Primary = 0.2462 m³/s @ 0.46 hrs, Volume= 569.8 m³

Routing by Stor-Ind method, Time Span= 0.00-9.00 hrs, dt= 0.01 hrs
 Starting Elev= 0.200 m Surf.Area= 270.0 m² Storage= 54.0 m³
 Peak Elev= 1.270 m @ 0.46 hrs Surf.Area= 270.0 m² Storage= 342.8 m³ (288.8 m³ above start)

Plug-Flow detention time= 22.9 min calculated for 515.8 m³ (90% of inflow)
 Center-of-Mass det. time= 18.9 min (35.9 - 17.0)

| Volume | Invert | Avail.Storage | Storage Description |
|--------|---------|---------------|--|
| #1 | 0.000 m | 378.0 m³ | 1.00 mW x 270.00 mL x 1.40 mH Prismatoid |

| Device | Routing | Invert | Outlet Devices |
|--------|---------|---------|--|
| #1 | Primary | 0.200 m | 300 mm Vert. Orifice/Grate Tube C= 0.820 |

Primary OutFlow Max=0.2462 m³/s @ 0.46 hrs HW=1.269 m (Free Discharge)
 1=Orifice/Grate Tube (Orifice Controls 0.2462 m³/s @ 3.48 m/s)

Pond 2P: Cistern Storage

